



404-669-8269



www.hapeville.org

3468 North Fulton Avenue, Hapeville, Georgia 30354

SUBMITTAL CHECKLIST PLANNING COMMISSION APPLICATION

- Submit complete APPLICATION with notarized signatures.
- Submit notarized AUTHORIZATION(S) OF PROPERTY OWNER (S).
- Submit AUTHORIZATION OF ATTORNEY, if an attorney is filing the application on behalf of a property owner.
- Submit a WRITTEN SUMMARY of the necessity for this action.
- Submit a SCALED OR DIMENSIONED BOUNDARY SURVEY showing the subject property.
- Submit a LEGAL DESCRIPTION of the land, by lot, block, and subdivision designations; by metes and bounds if no subdivision designations exist.
- Submit a SITE PLAN DRAWN TO SCALE depicting the proposed property.
 - Must comply with ordinance requirements for site plan review (Section 93-2-16)
 - Complete and submit the enclosed Site Plan Checklist
- Submit a TREE PLAN in compliance with the City of Hapeville Tree Ordinance.
 - Reference documents:
 - City of Hapeville Tree Ordinance
 - Tree Ordinance Plan Checklist
- Send an ELECTRONIC COPY of the full application and plans to:

 Department of Economic Development at

 <u>planningapplications@hapeville.org</u>
- Pay application fee A non-refundable fee, payable to the City of Hapeville: \$400.00 base fee, plus \$25.00 per acre, or \$25.00 per lot, or \$25.00 per unit (MR, T-House), whichever is greater. Fees are subject to change
- Incomplete applications will not be scheduled for Planning Commission review. Applications are only accepted when all materials are submitted and the required fee is paid in full.

CITY OF HAPEVILLE ECONOMIC DEVELOPMENT DEPARTMENT

Notary Public

Date Received:
Application # ———
ees:

PLANNING COMMISSION APPLICATION

ame of Applicant Iailing Address elephone	Email
elephone Mobile # roperty Owner (s)	Email
roperty Owner (s) Iailing Address	
Iailing Address	
elephone Mobile #	
	Email
ddress/Location of Property:	
arcel I.D. # (Information must be provided) resent Zoning Classification:	
resent Land Use	
lease check the following as it applies to this application	
Site Plan Review	Temporary Use Permit
Conditional Use Permit	Special Use Permit
Other (Please State)	
eby make application to the City of Hapeville, Georgia for the firm that the information provided here and above is true, co curacies may be considered just cause for invalidation of ication. I understand that the City of Hapeville, Georgia, reserver understand that it is my/our responsibility to conform with by acknowledge that all requirements of the City of Hapevillesh language and/or this document has been read and expleted this application. I understand that it is a felony to meville, Georgia pursuant to O.C.G.A. 16-10-20 and I may be prosected.	mplete and accurate, and I understand that a this application and any action taken on the ves the right to enforce any and all ordinances ith all of City of Hapeville's Ordinances in full e shall be adhered too. I can read and write the plained to me and I have full and voluntary take false statements or writings to the City
	Applicant's Signature
Sworn to and subscribed before me	Date:
This day of , 20	

PLANNING COMMISSION APPLICATION

WRITTEN SUMMARY

PLANNING COMMISSION APPLICATION

AUTHORIZATION OF PROPERTY OWNER


I CERTIFY THAT I AM THE	OWNER OF THE PROPERTY LOCATED AT:
City of Hapeville, County	of Fulton,State of Georgia
THE APPLICANT NAMED	MATTER OF THIS APPLICATION. I AUTHORIZE BELOW TO ACT AS THE APPLICANT IN THE ATION FOR PLANNING COMMISSION REVIEW
Name of Applicant	
Adress of Applicant ——	
Telephone of Applicant	
	Signature of Owner
	Print Name of Owner
Personaly Appeared Befo	ore Me
Thisday of	, 20
Notary Public	

PLANNING COMMISSION APPLICATION

	ate			
		<u>AUTHO</u>	RIZATION C	OF ATTORNEY
AUTHO		HE OWNER	R(S) TO FILE	ATTORNEY-AT-LAW, I HAVE BEEN E THE ATTACHED APPLICATION
	ity of Hapev	ville, Coun	ty of Fulto	n,State of Georgia
				Name of Attorney
				Bar Number:
				Address
				Telephone

SITE PLAN CHECKLIST - PLEASE INCLUDE WITH YOUR APPLICATION.

A site plan is used to determine the practical ability to develop a particular property within the City of Hapeville. Information relating to environmental condition, zoning, development impact, consistency with the Hapeville Comprehensive Plan and relevant town master plans will be considered in the decision process. To be considered, a site plan must contain the following information:



The locations, size (sf), and height (ft) of all existing and proposed structures on the site. Height should be assessed from the base of the foundation at grade to the peak of the tallest roofline.

Site plans shall include the footprint/outline of existing structures on adjoining properties. For detached single-family residential infill development, the front yard setback shall be assessed based on the average setback of existing structures on adjoining lots. Where practical, new construction shall not deviate more than ten (10) feet from the average front yard setback of the primary residential structure on an adjoining lot. Exemption from this requirement due to unnecessary hardship or great practical difficulty can be approved at the discretion of the Planning Commission. To be considered for an exemption, the applicant must submit a "Request for Relief" in writing with their site plan application, including the conditions that necessitate relief (i.e. floodplain, wetland encroachment, excessive slope, unusual lot configuration, legally nonconforming lot size, unconventional sitting of adjoining structures, etc).

The location and general design cross-section characteristics of all driveways, curb cuts and sidewalks including connections to building entrances. A walkway from the primary entrancedirectly to the public sidewalkis required for all single-family residential development.
The locations, area and number of proposed parking spaces. Please refer to Article 22.1 Chart of Dimensional Requirements to determine the correct number of parking spaces for your particular type of development.
 Existing and proposed grades at an interval of five (5) feet or less.
The location and general type of all existing trees over six (6) inch caliper and, in addition, an identification of those to be retained. Requirements for the tree protection plan are available in Code Section 93-2-14(f). Please refer to Sec. 93- 2-14(y) to determine the required tree density for your lot(s)
A Landscape Plan: The location and approximate size of all proposed plant material to be used in landscaping, by type such as hardwood deciduous trees, evergreen trees, flowering trees and shrub masses, and types of ground cover (grass, ivies, etc.). Planting in parking areas should be included, as required in Section 93-23-18.
The proposed general use and development of the site, including all recreational and open space areas, plazas and major landscape areas by function, and the general location and description of all proposed, outdoor furniture (seating, lighting, telephones, etc.). Detached single-family residential development may be exempt from this requirement.
The location of all retaining walls, fences (including privacy fences around patios, etc.) and earth berms. Detached single-family residential development may be exempt from this requirement.

	The identification and location of all refuse collection facilities, including screening to be provided. Detached single-family residential development may be exempt from this requirement.
	Provisions for both on-site and offsite storm-water drainage and detention related to the proposed development
	Location and size of all signs. Detached single-family residential development may be exempt from this requirement
	Typical elevations of proposed building provided at a reasonable scale (1/8" = 1'0") and include the identification of proposed exterior building materials. Exterior elevations should show all sides of a proposed building.
	Site area (square feet and acres).
	Allocation of site area by building coverage, parking, loading and driveways, and open space areas, including total open space, recreation areas, landscaped areas and others. Total dwelling units and floor area distributed generally by dwelling unit type (one-bedroom, two-bedroom, etc.) where applicable.
	Floor area in nonresidential use by category. Detached single-family residential development may be exempt from this requirement.
	Total floor area ratio and/or residential density distribution.
	Number of parking spaces and area of paved surface for parking and circulation.
	At the discretion of the planning commission, analyses by qualified technical personnel or consultants may be required as to the market and financial feasibility, traffic impact, environmental impact, storm water and erosion control, etc. of the proposed development.
information	each item on the list above certifying the all required has been included on the site plan, sign and submit this form the plan application. Failure to include this form and information

your application.

Applicant Signature: ______

Date: _____

required herein may result in additional delays for the consideration of